

## PROJECT

**Year:** 2003-2004

**No.:** 6412

**Client:**  
Køge Biopillefabrik,  
Denmark

**Subject:**  
The ship loading plant handles pellets of wood and straw from existing conveyor plant to a barge. The plant includes 2 mobile link conveyors, 1 mobile ship loader incl. ship loader chassis. The pellets are conveyed to the barge through a hopper with a funnel.

**Capacity:**  
600 tons/h

**Weight:**  
93 tons

## PROJEKT

**År:** 2003-2004

**Nr.:** 6412

**Bygherre:**  
Køge Biopillefabrik,  
Denmark

**Emne:**  
Udskibningsanlæggets opgave er at transportere træ- og halmpiller fra ekst. transportanlæg ud til en pram. Anlægget består af 2 stk. mobile linkconveyors, 1 stk. mobil skibslaster med skibslaster-chassis. Træ- og halmpillerne føres til pram gennem en tragt, som er påmonteret en bælg.

**Kapacitet:**  
600 tons/time

**Vægt:**  
93 tons

## Shiploading Equipment Skibslaster til skibslasteanlæg

